



CITY OF PLANO COUNCIL AGENDA ITEM

CITY SECRETARY'S USE ONLY					
<input type="checkbox"/> Consent <input type="checkbox"/> Regular <input type="checkbox"/> Statutory					
Council Meeting Date:		06/23/2014			
Department:		Public Works/David Falls			
Department Head		Gerald Cosgrove			
Agenda Coordinator (include phone #): Shawn Breen (972.769.4193)					
CAPTION					
Bid No. 2014-224-B, for the Guardrail Repair Project 6318 to Vann/Elli, Inc., in the amount of \$179,550 and authorizing the City Manager or his authorized designee to execute all necessary documents.					
FINANCIAL SUMMARY					
<input type="checkbox"/> NOT APPLICABLE <input type="checkbox"/> OPERATING EXPENSE <input type="checkbox"/> REVENUE <input checked="" type="checkbox"/> CIP					
FISCAL YEAR:	2013-14	Prior Year (CIP Only)	Current Year	Future Years	TOTALS
Budget		0	180,000	100,000	280,000
Encumbered/Expended Amount		0	0	0	0
This Item		0	-179,550	0	-179,550
BALANCE		0	450	100,000	100,450
FUND(S): CAPITAL RESERVE CIP					
<p>COMMENTS: Funds are available in the 2013-14 Capital Reserve CIP. This item, in the amount of \$179,550 will leave a current year balance for the Traffic Guardrails project of \$450.</p> <p>STRATEGIC PLAN GOAL: Repairing guardrail systems that have been damaged or malfunctioned relates to the City's goal of Safe Large City.</p>					
SUMMARY OF ITEM					
<p>Staff recommends the bid for the Guardrail Repair Project to Vann/Elli, Inc., in the amount of \$179,550.00, be accepted as the lowest responsible bid for the project conditioned upon timely execution of all necessary documents.</p> <p>This project involves the repair of guardrail systems in various locations throughout the City of Plano.</p> <p>Engineer's estimate for this project is \$346,800.00</p> <p>2,160 companies were invited to bid this project and 25 companies looked at the bidding documents.</p>					
List of Supporting Documents: Bid Recap; Location List			Other Departments, Boards, Commissions or Agencies		

CITY OF PLANO

BID NO. 2014-224-B Guardrail Repair Project No. 6318 Bid Recap

Bid opening Date/Time: May 6, 2014 @ 1:30PM

Number of Vendors Notified: 2166

Vendors Submitting "No Bids": 0

Bids Evaluated Non-Responsive to Specification: 0

Number of Bids Submitted: 1

<u>Vendor Name</u>	<u>Total Bid</u>
Vann/Elli, Inc.	\$179,550.00

Recommended Vendor(s):
Vann/Elli, Inc. \$179,550.00

Nancy Corwin

May 6, 2014

Nancy Corwin, Buyer

Date

GUARD RAIL REPAIR LOCATION LIST

1. Alma Road South Bound over Spring Creek Channel, inside lane, approach
Repair and/or Replace 25 LF of West Beam Guard Rail
2. Alma Road North Bound at SH 190, inside lane, approach
Remove and/or Replace 1 Timber Post with concrete foundation
3. Alma Drive South Bound at State Highway 190, inside lane, approach
Remove and/or Replace 1 Timber Post without concrete foundation
4. Alma Drive South Bound over Russell Creek Channel, inside lane, down stream
Remove and Replace 4 Timber Post without concrete
5. Alma Drive, South Bound over Russell Creek Channel, outside lane, downstream
Remove and Replace 4 Timber Posts without concrete
6. Alma Drive, South Bound over Russell Creek Channel, outside lane, approach
Remove and Replace 4 Timber Posts without concrete
7. Alma Drive, South Bound over Russell Creek Channel, inside lane, approach
Remove and Replace 4 Timber Posts without concrete
8. K Avenue, North Bound at Westminster Drive
Repair impact damage and remove and replace 1 Timber Post
9. K Avenue, North Bound north of Westminster Drive at Datamatic driveway
Remove and Replace 1 Timber Post without concrete
10. K Avenue, South Bound at Well's Brothers Farm Store
Replace blunt end cap
11. K Avenue, North Bound over Rowlett Creek Channel, approach
Remove and Replace 25 LF of West Beam Guard Rail
12. K Avenue, North Bound at 12th Street
Repair and/or Replace 15' of curved West Beam Guard Rail Section
13. Custer Road, North Bound at Rustic Drive, approach
Replace 2 Timber Posts

14. Custer Road, North Bound at Russell Creek Channel, approach
Remove and Replace 1 Timber Post, Remove and Replace 1 Steel Post with concrete foundation, Remove and Replace 3 wood block outs, Remove and Replace 1 Steel block out, Repair/Replace 75 LF of West Beam Guard Rail
15. Custer Road, North Bound at Driveway to Kinko's
Remove and Replace 4 Timber Posts
16. Custer Road, North Bound, north of 15th Street
Remove and Replace 5 Timber Posts
17. Custer Road, North Bound at Ridgeview Drive, inside lane, approach
Repair and/or Replace 25 LF of West Beam Guard Rail
18. Hedcoxe Road, West Bound at Russell Creek Channel, outside lane
Replace Terminal Anchor Post
19. Jupiter Road, North Bound between Creekcove Drive and Briarwood Drive
Repair 10 LF of West Beam Guard Rail
20. Jupiter Road, South Bound, north of Parker Road approach
Repair downstream terminal Rail
21. Legacy Drive, East Bound, east of Ohio Drive
Replace 3 Timber Posts without concrete
22. McDermott Road, East Bound at Rockledge Lane, inside lane
Remove and Replace 6 Timber Break Away Post with concrete foundation
Repair and/or Replace 25 LF of West Beam Guard Rail, Remove and Reset Single Guardrail Terminal Impact Head, Replace Single Guardrail Terminal Object Marker, Replace Single Guardrail Terminal Cable Anchor, Replace Single Guardrail Terminal strut, Remove and Replace 7 Block Outs
23. Ohio Drive North Bound, north of Spring Creek Parkway approach
Remove and Replace 1 Timber Post, Repair and/or Replace 25 LF of West Beam Guard Rail, supply and install on blunt end cap
24. Ohio Drive South Bound, south of Plano Parkway at RR Crossing
Repair and/or Replace 3 Timber Posts
25. Parkwood Drive, South Bound at dead end with Tiburon Drive
Remove and Replace 11 Timber Posts

26. Park Boulevard, East Bound at Rowlett Creek, outside lane, downstream
Remove and Reset Terminal Anchor Post
27. Park Boulevard, East bound over US 75, outside lane, approach
Remove and Replace 4 Timber Posts without concrete
28. Park Boulevard, East Bound over US 75, downstream, outside lane
Remove and Replace 50 Timber Posts without concrete
29. Park Boulevard, East Bound over Spring Creek Channel, inside lane,
downstream
Remove and Replace 8 Timber Posts without concrete
30. Park Boulevard, East Bound over Spring Creek Channel, outside lane,
downstream
Remove and Replace 8 Timber Posts
31. Park Boulevard, East Bound over Spring Creek Channel, outside lane,
downstream
Remove and Replace 7 Timber Posts without concrete, Remove and
Replace 4 Timber Posts with concrete
32. Park Boulevard, East Bound at White Rock Creek Channel, outside lane,
downstream
Remove and Replace 2 Timber Posts and attach one Timber Post to
Guard Rail, Repair or Replace 25 LF of Guard Rail
33. Park Boulevard, West Bound at White Rock Creek Channel, outside lane,
downstream
Remove and Replace 36 Timber Posts without concrete
34. Park Boulevard, West Bound at Mira Vista Boulevard, outside lane
Remove and Replace 221 Timber Posts and Supply and install 3 Timber
Posts
35. Park Boulevard, East Bound at Mira Vista Boulevard
Remove and Replace 3 Timber Posts, Reattach 5 Timber Posts
36. Park Boulevard, East Bound at Rowlett Creek, outside lane, approach
Remove and Reset Terminal Anchor Post
37. Parker Road, East Bound at San Gabriel Drive
Repair and/or Replace 25 LF of West Beam Guard Rail, Straighten 2
Timber Posts

38. Parker Road, West Bound at White Rock Creek, outside lane, downstream
Remove and Replace 5 Steel Posts with concrete foundation, Replace 266 LF of modified T 101 Railing, Replace West Beam Guard Rail coupling
39. Parker Road, West Bound at White Rock Creek, outside lane, approach.
Remove and Replace 5 Timber Posts with concrete foundations, Repair 100 LF of West Beam Guard Rail at 2 locations, Remove and Replace Single Guard Rail Terminal Rail
40. Parker Road, West Bound at White Rock Creek, outside lane, downstream
Remove and Replace 5 Timber Posts with concrete foundation
41. Parker Road, East Bound, east of Jupiter Road
Remove and Replace 1 Timber Post without concrete, Repair and/or Replace 25 LF of West Beam Guard Rail, Replace 25 LF of Single Guard Rail Terminal Rail
42. Plano Parkway, West Bound at Mira Vista Drive, down stream
Remove and Replace 60 Timber Posts without concrete, Repair 25 LF West Beam Guard Rail
43. Plano Parkway, West Bound at Mira Vista Drive, approach
Remove and Replace 43 Timber Posts without concrete
44. Plano Parkway, East Bound, east of Mira Vista Drive, approach
Remove and Replace 61 Timber Posts without concrete
45. Plano Parkway, West Bound, east of Independence Parkway, approach
Remove and Replace 2 Timber Posts without concrete
46. Shiloh Road, South Bound at Rockbrook Drive
Remove and Replace 13 Timber Posts without concrete
47. Shiloh Road, North Bound at Rockbrook Drive
Remove and Replace 8 Timber Posts without concrete
48. Spring Creek Parkway West Bound, inside lane, approach at Meadowlands Drive
Repair and/or Replace 50 LF of West Beam Guard Rail, straighten all posts
49. Spring Creek Parkway, East Bound, east of Custer Road, upstream
Remove and Replace 1 Steel Post with concrete foundation

50. Spring Creek Parkway, West Bound, east of Custer Road
Replace 1 Timber Post
51. Spring Creek Parkway, West Bound at Spring Creek Channel, outside lane, approach
Replace 80 LF of West Beam Guard Rail, Remove and Replace 8 Break Away Timber Posts and 8 Timber Posts with Block Outs, Remove and Reset ET 200 Impact Head, Replace ET 200 Object Marker, Replace ET 200 cable anchor and Replace ET 200 strut
52. Spring Creek Parkway, East Bound at Spring Creek channel, outside lane, approach
Remove and Replace 2 Timber Break Away Posts, Repair 50 LF of West Beam Guard Rail, Remove and Reset ET 200 Impact Head, Replace ET 200 Object Marker, Replace ET 200 cable anchor, Replace ET 200 strut
53. Spring Creek Parkway, West Bound north of Park, outside lane, approach
Remove and Replace 1 Timber Post.
54. Spring Creek Parkway West Bound, outside lane, approach
Repair and/or Replace 2 Timber Posts, Remove and Reset Single Guardrail Terminal Impact Head
Replace Single Guardrail Terminal Object Marker, Replace Single Guardrail Terminal Cable Anchor, Replace Single Guardrail Terminal Strut
55. Windhaven Parkway, south of Spring Creek Parkway
Remove and Replace 1 Timber Post and Straighten 1 Timber Post
56. 15th Street, East Bound at Gables Court
Replace 1 Timber Post without concrete
57. 14th Street, West Bound at Rowlett Creek, approach
Repair and/or Replace 25 LF of West Beam Guardrail, Remove and reset Single Guardrail Terminal Impact Head
58. 14th Street, East Bound at Rowlett Creek, approach
Repair 25 LF of West Beam Guard Rail, Remove and Reset Single Guardrail Terminal Impact Head, Replace Single Guardrail Terminal Cable Anchor and Single Guardrail Terminal Strut